

Furnizor: **Sc Trivolt Distribution SRL**
Reg. com.: J23/3300/2016
CIF: RO36421140
Adresa: Strada Apusului nr 3 (primul
sens giratoriu Tehodor Pallady-
Autostrada Soarelui), Catelu, Ilfov
Banca: BRD
IBAN: RO34BRDE441SV13182234410



**LEGRAND OTO - FTTH PREWIROSU/PRETERMINATED - 4 OF - 4
SC/APC FEEDTHROUGHS - 25 M CABLE**

Caracteristici tehnice

Optical telecommunications outlet (OTO) - prewired and preterminated

The OTO is the termination point of the FTTH installation in the home

It is fixed in the home network cabinet and enables connection to the operator router

The prewired and preterminated version enables direct connection to the BEP via the connectors for tool-free mounting on-site

The pulling cord makes it easy to use in the riser and in conduits (Ø20 mm recommended)

Technical characteristics:

For fixing on DIN rail or wall

Preterminated at both ends

G657A2 900 µm

Cable diameter: 4.2 mm

Pulling cord diameter: 13 mm

Prewired and preterminated OTO - 4 OF

OTO with 4 SC/APC feedthroughs + 25 m of cable preterminated at both ends

Caracteristici generale

Ftth - Fibre to the Home - preterminated solution

The preterminated solution has been specially designed for make Ftth available to all installers

It requires no special equipment (does not require a device for slicing the fibre)

It is recommended for buildings of average height (up to 12 apartments)

Pret: 0,00 lei (TVA inclus)

Detalii online: <https://www.materialeelectrice.ro/oto-ftth-prewirosu-preterminated-4-of-4-sc-apc-feedthroughs-25-m-cable-231176>