



LEGRAND TABLOU METALIC MODULAR XL³ S 160 MONTAJ INCASTRAT 24-MODULE PE RAND CU FIXING LUGS - RAL 9003 - 3 RANDURI - 72 MODULE - 662X667X138 MM

Caracteristici tehnice

Montaj incastat 24-module per row cabinets

Supplied with fixing lugs

Faceplates: RAL 9003

Number of rows : 3

Numar de module : 72

Height : 662 mm

Width : 667 mm

Depth : 138 mm

Caracteristici generale

XL³ S 160 - 24 module per row - "ready to use" metal distribution cabinets

Cabinets supplied with rails fitted (150 mm fixing centres) and full height faceplates

Doors and terminal blocks to be ordered separately

Take DPX³ 160 and modular protection devices

Used to create assemblies certified IEC 61439-2 and -3

IP 40 with door

IP 30 without door

Cut-outs in top and bottom for feeding cables through

Can take Lina 25 ducting

Pret: 1.509,49 LEI (TVA inclus)

Detalii online: <https://www.materialelectrice.ro/tablou-metalic-modular-xl3-s-160-montaj-incastat-24-module-pe-rand-cu-fixing-lugs-ral-9003-3-randuri-72-module-662x667x138-mm-236352>